

SUNY Oswego SWPPP

SUNY at Oswego
Oswego, New York



This project focused on the need for repairing and replacing both pedestrian and vehicular facilities, while improving circulation on the east side of campus as it relates to other on-going projects on campus. This project provided an expanded parking lot (approximately 130 new spaces) for faculty and staff to the west of the existing Poucher Hall parking lot to replace parking being removed as part of a new science building; including associated drainage, lighting, landscaping and stormwater design. The project provided a new walkway from Campus Center to Centennial Drive and provided a Campus Center Plaza with landscaping on the ground floor of the lakeside of the Campus Center for outside events.

Design of a parking lot expansions included:

- Providing NOI and SWPPP for construction.
- Temporary Soil and Erosion Control Plans and Details developed in accordance with NYSSSESCM Manual.
- Post Construction Stormwater Plans included Grass Swales and Pocket Pond.
- Weekly Stormwater Inspection was overseen and monthly status reports produced.
- A post construction maintenance plan was implemented.
- Drainage report for existing parking lot was also prepared.